

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-21,061-0001

LEASE NAME Morrison Trust

WELL NUMBER #1 SWD

SPOT LOCATION SW SW NW

SEC. 1 TWP. 21S RGE. 14W (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 4-9-86

Plugging Completed 4-22-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Energy Three, Inc.

ADDRESS Box 1505 Great Bend, Kansas 67530

PHONE # (316) 792-5968 OPERATORS LICENSE NO. 5430

Character of Well SWD
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3638'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	263'	none
				5-1/2"	3636'	1994'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3334' and 5 sacks cement. Shot pipe @2909', 2606', 2431', 2214', 1994' and pulled a total of 49 joints of 5-1/2" casing. Plugged surface with 3 hulls, 15 gel, 70 cement, 10 gel, 1 hull and 100 cement, 60/40 pos, 6% gel, 3% cc. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 24 day of April, 1986

IRENE HOOVER
State of Kansas
My Appt. Exp. Aug. 15, 1989

My Commission expires: _____

Irene Hoover
Notary Public

DRILLERS LOG

June 6, 1980

#1 Morrison
 SW SW NW
 Sec. 1-21S-14W
 Stafford Co., Kansas


OPERATOR: Energy Three, Inc.
 CONTRACTOR: B & B Drilling, Inc.
 COMMENCED: May 27, 1980
 COMPLETED: June 2, 1980

8 5/8" @ 263' w/225 sx

0	778	Sand & Shale
778	2022	Shale
2022	3638	Lime & Shale
3638		RTD 5 1/2" @ 3636' w/100 sx


We certify that the above and foregoing is a true and correct copy of the log on the #1 Morrison located in Stafford County, Kansas.

B & B DRILLING, INC.



 Bill Lahar President

Subscribed and sworn to before me this 6th day of June, 1980.



 Betty M. Abbott Notary Public


RECEIVED
 STATE CORPORATION COMMISSION

APR 11 1986

CONSERVATION DIVISION
 Wichita, Kansas