


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 1 Twp. 21S. Rg. 14W (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SE SW
Lease Owner ALPINE OIL & ROYALTY CO., INC.
Lease Name Morrison Well No. 9
Office Address 800 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed 1-8-61 19
Application for plugging filed 1-8-61 19
Application for plugging approved 1-8-61 19
Plugging commenced 1-8-61 19
Plugging completed 1-8-61 19
Reason for abandonment of well or producing formation non productive

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3720 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	283'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud from total depth 3720 feet to 270 feet
plug of hulls and Halliburton plug and 25 sacks cement
through drill pipe. Heavy mud to 40 feet and
another plug of hulls and Halliburton plug 10 sacks
cement - 2 sacks to plug rat hole

RECEIVED
STATE CORPORATION COMMISSION

JUL 10 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Quaker Drilling Co., Inc.
Address 800 Bitting Building, Wichita, Ks.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul
800 Bitting Building, Wichita, Ks.

SUBSCRIBED AND SWORN to before me this 9th day of July, 1963

My commission expires August 10, 1965
Virginia Merrill
Notary Public.

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: 12-31-60

CONTRACTOR: Quaker Drilling Co., Inc.

Completed: 1-8-61

Morrison No. 9-A
SW SE SW Sec. 1-21S-14W
Stafford County, Kansas

Elevation: 1919

Production: D & A

Casing Record

Set 8 5/8 inch casing at 283 feet with 275 sacks cement

(Figures Indicate the Bottom of the Formations)


FORMATION	DEPTH	FORMATION TOPS	
Surface Soil & Sand	225	Heebner	3218 -1299
Shale and Shells	285	Brown Lime	3338 -1319
Shale and Sand	430	Lansing	3349 -1330
Red Bed	817	Base of Kansas City	3579 -1654
Anhydrite	840	Viola	3579 -1660
Shale and Shalls	1670	Simpson	3642 -1723
Sandy Lime and Shale	1725	Arbuckle	3694 -1775
Lime and Shale	2040	Rotary Total Depth	3720 -1801
Sandy Lime and Shale	2210		
Lime and Shale	3290		
Shale	3339		
Lime and Shale	3395		
Lime	3515		
Lime and Shale	3570		
Lime, Chert & Shale	3720		

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the SW SE SW Section 1-21S-14W, Stafford County, Kansas.

QUAKER DRILLING CO., INC.

By: 

Subscribed and Sworn to before me a Notary Public this 9th day of July, 1963.


Virginia Mundell, Notary PublicMY COMMISSION EXPIRES:
August 10, 1965**RECEIVED**
STATE CORPORATION COMMISSION

JUL 10 1963

CONSERVATION DIVISION
Wichita, Kansas