


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 1 Twp. 21S Rge. 14W (E) (W)
Location as "NE/CNW/SW" or footage from lines. NE NE NW
Lease Owner ALPINE OIL & ROYALTY CO., INC.
Lease Name Morrison "B" Well No. 1
Office Address 800 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed November 14, 1965 19
Application for plugging filed November 14, 1965 (phone) 19
Application for plugging approved November 14, 1965 (phone) 19
Plugging commenced November 14, 1965 19
Plugging completed November 14, 1965 19
Reason for abandonment of well or producing formation non-productive in commercial quantities
If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3630 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	290'	cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud from total depth, 3630 feet, to 285 feet.
First plug at 285 feet with 1/4th sack hulls and 20 sacks of cement. Heavy mud to 40 feet. Second plug at 40 feet and 10 sacks of cement and 1/4th sacks hulls. 2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

NOV 22 1965

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.
Address 800 Bitting Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dwight J. Wilson (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dwight J. Wilson
800 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of November 19 65

My commission expires August 10, 1969

Virginia Mundell
Notary Public.

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

MORRISON "B" #1
 NE NE NW SECTION 1-21S-14W
 STAFFORD COUNTY, KANSAS

COMMENCED: NOVEMBER 6, 1965
 COMPLETED: NOVEMBER 15, 1965

OPERATOR - ALPINE OIL & ROYALTY Co., INC.

DEPTH		FORMATION	REMARKS
FROM	TO		
0	240	SAND, CLAY AND SHELLS	
240	290	BLUE SHALE	RAN 290' OF 8-5/8" CASING, SET @ 290' w/285 SACKS CEMENT.
290	415	SHALE, SAND AND RED BED	
415	800	SHALE AND SHELLS	
800	825	ANHYDRITE	
825	1600	SHALE AND SHELLS	
1600	2985	SHALE AND LIME	
2985	3630	LIME	
3630	TD		DRY AND ABANDONED.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE NE NE NW SECTION 1-21S-14W, STAFFORD COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall

E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 16TH DAY OF NOVEMBER, 1965, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
 BARBARA J. LAYTON, NOTARY PUBLIC

My Commission Expires February 1, 1968.

RECORDED
 NOV 22 1965
 CONSERVATION DIVISION
 WICHITA, KANSAS