


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Stafford

County. Sec. 1 Twp. 21S Rge. 14W (E) (W)Location as "NE/CNW/SW" or footage from lines. NW SW NELease Owner ALPINE OIL & ROYALTY CO., INC.Lease Name MORRISONWell No. 2-BOffice Address 800 Bitting Building, Wichita, KansaCharacter of Well (completed as Oil, Gas or Dry Hole) dry holeDate well completed November 28, 1959

19

Application for plugging filed November 28, 1959

19

Application for plugging approved November 28, 1959

19

Plugging commenced November 28, 1959

19

Plugging completed November 28, 1959

19

Reason for abandonment of well or producing formation non-productive in commercial quantities

If a producing well is abandoned, date of last production

19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YesName of Conservation Agent who supervised plugging of this well Frank BroadfootProducing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3610 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 280 | Cemented |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud from total depth to surfaceSolid plug at 270 feet with 30 sacks cementHeavy mud to 40 feet - another plug and 10 sacks cement to base of cellar

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Quaker Drilling Co., Inc.Address 800 Bitting Building, Wichita, KansasSTATE OF Kansas, COUNTY OF Sedgwick, ss.
Dwight J. Wilson

(employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dwight J. Wilson800 Bitting Building, Wichita, Kansas
(Address)SUBSCRIBED AND SWORN TO before me this 7th day of December, 1959My commission expires August 10, 1961

Notary Public.

15.185.00364.0006

RECEIVED
STATE CORPORATION COMMISSION

DEC 8 1959

CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: November 18, 1959

Contractor: Quaker Drilling Co., Inc.

Completed: November 28, 1959

Morrison No. 2-B
NW SW NE Sec. 1-21S-14W
Stafford County, Kansas

Elevation: 1917 KB

Production: D. & A.

Casing Record

Set 8 5/8 inch casing at 280 feet with 300 sacks cement

(Figures Indicate the Bottom of the Formations)

| <u>FORMATION</u> | <u>DEPTH</u> | <u>FORMATION TOPS</u> |
|----------------------|--------------|--------------------------------|
| Surface Soil | 30 | Heebner 3185 -1268 |
| Sand | 220 | Brown Lime 3299 -1382 |
| Shale | 280 | Lansing 3309 -1392 |
| Shale and Red Bed | 799 | Base of Kansas City 3527 -1610 |
| Anhydrite | 825 | Simpson Shale 3548 -1631 |
| Shale and Shells | 1525 | Simpson Sand 3556 -1639 |
| Sandy Lime and Shale | 1750 | Arbuckle 3597 -1680 |
| Lime and Shale | 2185 | Rotary Total |
| Shale and Shells | 2650 | Depth 3610 -1693 |
| Lime and Shale | 3300 | |
| Lime | 3505 | |
| Lime and Shale | 3556 | |
| Lime, Shale and Sand | 3569 | |
| Lime and Shale | 3597 | |
| Dolomite | 3610 | |

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the test drilled in the NW SW NE of Section 1, Township 21 South, Range 14 West, Stafford County, Kansas.

QUAKER DRILLING CO., INC.

By: Dwight J. Wilson
Dwight J. Wilson, Secretary

SUBSCRIBED AND SWORN to before me a Notary Public this 7th day of December, 1959.

Virginia Mandell
Virginia Mandell, Notary Public

MY COMMISSION EXPIRES:
August 10, 1961