

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Stafford County. Sec. 1 Twp. 21 Rge. 14 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C-NE-NE-NE
Lease Owner Plains Exploration Company
Lease Name Morrison Well No. 2
Office Address Denver 2 Colorado
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-7-51 19
Application for plugging filed 5-7-51 19
Application for plugging approved 5-7-51 19
Plugging commenced 5-7-51 19
Plugging completed 5-7-51 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Harold Hollis
Producing formation Depth to top Bottom Total Depth of Well 55 95 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	234'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with heavy mud to 230'. Set plug, mixed and poured 15 sks. of cement through drillpipe. Filled to 30' below top of surface pipe plug placed at 30' and filled to top of surface with cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 16 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Plains Exploration Company
Address 525 University Bldg.
Denver 2, Colorado

STATE OF Kansas, COUNTY OF Stafford, ss.
E. E. Duncan (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) *E. E. Duncan*
Stafford, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 11th day of May, 1951

My commission expires Aug 4 - 1954 Notary Public.

PLUGGING
FILE SEC-1-T-21-R144
BOOK PAGE 80 LINE 13

PLAINS EXPLORATION COMPANY
 DRILLERS WELL LOG
 MORRISON #2

Company -- Plains Exploration Company
 Farm -- Morrison #2

Sec. 1-T21S-R14W
 Loc. NE $\frac{1}{4}$ -NE $\frac{1}{4}$ -NE $\frac{1}{4}$
 County -- Stafford
 Elevation -- 1913 R. B.
 Production -- Dry Hole

Total Depth -- 3595'
 Commenced -- 4-27-51
 Shot or Treated -- none
 Contractor -- Petroleum Incorporated
 Completed -- 5-7-51

Casing Record

8 5/8" set at 234, cemented with 175 sacks

All measurements carried from Rotary Bushing.

0'	Rotary Bushing	Formation Tops
30'	Surface Soil and Clay	by the geologist
210'	S and and Clay	
234'	Blue Shale	Heebner 3176' (-1263)
262'	Shale	Brown Line 3293' (-1380)
320'	Sand	Kansas City 3304' (-1391)
800'	Red Bed	Base Kansas City 3522' (-1609)
825'	Anhydrite	Sand 3538' (-1623)
1050'	Shale and Shells	Simpson Shale 3551' (-1638)
1230'	Salt	Arbuckle 3574' (-1661)
1540'	Shale and Shells	
2080'	Lime and Shale	
2210'	Shale and Shells	
2555'	Lime and Shale	
2700'	Shale and Shells	
2790'	Lime and Shale	
2915'	Shale	
3005'	Shale and Lime	
3215'	Lime	
3293'	Shale	
3535'	Lime	
3547'	Sand	
3549'	Shale	
3595'	Lime	
3595'	T.D.	

Due to lack of saturation and odor, it was not recommended by the geologist that any shows be tested.

I HEREBY CERTIFY THE ABOVE IS A TRUE AND CORRECT RECORD OF THE DRILLERS LOG ON THIS WELL.

Signed *E. E. Duncan*

SUBSCRIBED AND SWORN TO BEFORE ME THIS 10th DAY OF MAY 1951

MY COMMISSION EXPIRES Aug 4 - 1954

[Signature]
 NOTARY PUBLIC

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 16 1951
 CONSERVATION DIVISION
 Topeka, Kansas

PLUGGING
 FOOT SEC. 1-T-21S-R14W
 BOOK PAGE 80 LINE 13