

STATE OF KANSAS  
STATE CORPORATION COMMISSION

## WELL PLUGGING RECORD

OR  
FORMATION PLUGGING RECORDStrike out upper line  
when reporting plug-  
ging off formations.Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

NORTH


Locate well correctly on above  
Section Plat

Stafford County. Sec. 1 Twp. 21S. Rge. 14W (E) (W)  
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. SW-SW-NE  
Lease Owner. Plains Exploration Company  
Lease Name. Morrison Well No. 1  
Office Address. Denver 2, Colorado  
Character of Well (completed as Oil, Gas or Dry Hole). Dry Hole  
Date well completed. Feb. 7, 1950 19  
Application for plugging filed. Feb. 7, 1950 19  
Application for plugging approved. Feb. 7, 1950 19  
Plugging commenced. Feb. 7, 1950 19  
Plugging completed. Feb. 8, 1950 19  
Reason for abandonment of well or producing formation. Dry Hole

If a producing well is abandoned, date of last production. 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well. Mr. Stough  
Producing formation. Depth to top. Bottom. Total Depth of Well. Feet  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	350'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from. feet to feet for each plug set.

Heavy mud circulated thru drill pipe

Placed Halliburton plug at 350'

Mixed 15 sks. of cement and run through drill pipe to top plug.

Filled hole to 30' with heavy mud.

Mixed 10 sks. of cement filled hole to bottom of cellar or  
4' below ground level.

**RECEIVED**  
Conservation Div.  
FEB 13 1950  
STATE CORPORATION  
COMMISSION  
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. Plains Exploration Company  
Address. 524 University Building  
Denver 2, Colorado

STATE OF Kansas, COUNTY OF Stafford, ss.

E. E. Duncan

(employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-  
described well as filed and that the same are true and correct. So help me God.

(Signature)

Stafford, Kansas


(Address)

SUBSCRIBED AND SWORN to before me this 9th day of February, 1950.

My Commission Expires July 24, 1952

My commission expires.

Notary Public.



PLAINS EXPLORATION COMPANY  
 DRILLERS WELL LOG  
 MORRISON #1

Company -- Plains Exploration Company  
 Farm -- Morrison

Sec. 1-21S-14W  
 Loc. SW/4-SW/4-NE/4

Total Depth -- 3626'  
 Commenced -- 1-22-50  
 Shot or Treated -- none  
 Contractor -- E. K. Carey  
 Completed -- 2-7-50

County -- Stafford  
 Elevation -- 1919 K. C.  
 Production -- Dry Hole

-----Casing Record-----

8 5/8" at 350' cemented with 225 sacks, circulated.

All measurments carried from Kelly Bushing.

0' Kelly Bushing  
 20' Soiland shale  
 218' Sand and shells  
 320' Shale and sand  
 710' Shale  
 1520' Shale and shells  
 1750' Shale and lime  
 2140' Lime  
 2205' Shale and shells  
 2455' Shale and lime  
 2806' Shale  
 2835' Sand  
 2874' Shale and sand and lime  
 3090' Lime  
 3150' Shale  
 3273' Lime  
 3326' Shale  
 3626' Lime

Geologists Tops

Offocial Tops not available to  
 me at the time of this log.

Drill Stem Test

First test from 3603' to 3610' tool  
 open 1 hour, recovered 40' of mud. Very  
 slight show of oil. Second test  
 from 3610' to 3626' tool open 25  
 minutes recovered 1910' of water.  
 Well abandoned.

I HEREBY CERTIFY THE ABOVE RECORD IS A TRUE AND CORRECT RECORD OF THE DRILLERS  
 LOG ON THIS WELL.


SIGNED

*E. E. Duncan*

SUBSCRIBED AND SWORN TO BEFORE ME THIS 9th DAY OF February 1950

MY COMMISSION EXPIRES My Commission Expires July 24, 1952

*Phyllis Henderson*  
 NOTARY PUBLIC



RECEIVED  
 Conservation Div.  
 FEB 13 1950  
 STATE CORPORATION  
 COMMISSION  
 KANSAS