

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Stafford County. Sec. 24 Twp. 21 Rge. 13 (X) (W)

Location as "NE/CNW/SW" or footage from lines C NW/4 SW/4 NW/4
Lease Owner Midstates Oil Corporation
Lease Name Bertha Hall Well No. 3
Office Address 518 Nat'l Bank of Tulsa Bldg., Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed April 18, 1952
Application for plugging filed June 23, 1952
Application for plugging approved June 26, 1952
Plugging commenced August 11, 1952
Plugging completed August 19, 1952
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Pratt, Kansas
Producing formation Arbuckle Depth to top 3616 Bottom _____ Total Depth of Well 3633 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	300	0
				5-1/2	3613	1970'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Baker Cast Iron Bridge Plug set @ 3355' - Filled w/ sand and gravel from 3355 to 3331
Cemented from 3331 to 3296. Mixed 15 sacks of Acquagel with Halliburton - Put Plug
on top of mud and mixed 80 sacks of cement. Filled hole from 240' to surface
with cement.

RECEIVED
CONSERVATION COMMISSION
AUG 30 1952
8-30-1952
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pipe Pulling, Inc.
Address Stafford, Kansas

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
W. H. Barclay (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. H. Barclay
518 N.B.T. Bldg., Tulsa, Oklahoma
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of August, 19 52
Betty June Sawyer Notary Public.

My commission expires My Commission Expires March 21, 1955

PLUGGING
FILE SEC 24 T 21 R 13
BOOK PAGE 26 LINE 6

CORPORATION COMMISSION
OF KANSAS

WELL RECORD

PRODUCER: Midstates Oil Corp., 518 Nat'l Bank of Tulsa Bldg., Tulsa, Oklahoma
 FARM NAME: Bertha Hall WELL NUMBER: Three (3) FIELD: West Mueller
 WELL LOCATION: C - NW/4 SW/4 NW/4 Sec. 24, 21S, 13W Trego County, Kansas
 DRILLING BEGAN: January 23, 1952 DRILLING COMPLETED: February 2, 1952
 PRODUCING FORMATION: Arbuckle Lime ELEV. 1870 KB

CASING RECORD

<u>Size Casing</u>	<u>Where Set</u>	<u>Number of Sacks of Cement</u>
8-5/8"	300'	225 Sacks
5-1/2"	3613'	150 Sacks

<u>Formation</u>	<u>Top</u>	<u>Bottom</u>
Shale & Sand	0	40
Sand	40	150
Sand & Shale	150	190
Shale & Shells	190	260
Red Bed	260	600
Shale & Sand	600	664
Sand	664	700
Shale & Shells	700	760
Shale, Red Bed, & Shells	760	1265
Salt, Shale & Shells	1265	1435
Shale & Shells	1435	1525
Lime & Shale	1525	3306
Lime	3306	3633
Total Depth		3633