

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Stafford County, Sec. 24 Twp. 21 Rge. 13 (E) (W)

Location as "NE/CNW/SSW" or footage from lines C NW SE NW

Lease Owner Midstates Oil Corporation

Lease Name Bertha Hall Well No. 2

Office Address Seventh Floor Midstates Bldg., Tulsa 3, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed March 5, 19 51

Application for plugging filed July 16, 19 55

Application for plugging approved _____ 19 _____

Plugging commenced August 10, 19 55

Plugging completed August 14, 19 55

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production June 30, 19 55

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren H. Horner

Producing formation Arbuckle Depth to top 3621 Bottom 3630 Total Depth of Well 3670 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	298'	0
				5-1/2"	3669'	1944'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled w/ sand & rock from 3669' to 3610' put 5 sacks cement plug on top of sand & rock w/ dump bailer from 3610' to 3569'. Filled w/ heavy mud from 3569' to 298'. Set 10' Rock Bridge from 298' to 288'. Dumped 20 sacks of cement w/ bailer from 288' to 241'. Filled w/ heavy mud from 241' to 41'. Bridged w/ rock & sand & cemented w/ 10 sacks of cement to surface of ground.

RECEIVED
STATE CORPORATION COMMISSION
AUG 25 1955
8-25-1955
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF OKLAHOMA, COUNTY OF TULSA, ss.
W. H. Barclay (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. H. Barclay
Midstates Bldg., Tulsa, Oklahoma
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of August, 19 55

My commission expires _____

Betty June Howey
BETTY JUNE HOWEY, Notary Public
in and for the State of Oklahoma
My Commission Expires March 21, 1959
Notary Public.

PLUGGING
FILE SEC. 24 T. 21 R. 13W
BOOK PAGE 134 LINE 39

24-2675-S 2.52-20M

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

15-185.00428.0000


COMPANY Midstates Oil Corporation

SEC. 24 T. 21S R. 13W
 LOC. C NW SE NW

FARM Bertha Hall NO. 2 (Two)

TOTAL DEPTH 3670'
 COMM. January 11, 1951 COMP. January 28, 1951
 SHOT OR TREATED Acidized w/ 6500 gal.
 CONTRACTOR B & R Drlg. Co.
 ISSUED August 22, 1955

COUNTY Stafford
 KANSAS



CASING
 20 10
 15 298' w/ 175 sax
 12 6
 13 3669' w/ 150 sax

ELEVATION 1866' DF

PRODUCTION
 State Potential-
 117 B.O. / 3% water
 in 24 hours pumpint

FIGURES INDICATE BOTTOM OF FORMATIONS

Formation	Top	Bottom
Sand & Shale	0	240
Shale & Red Bed	240	710
Anhydrite	710	725
Shale & Red Bed	725	1025
Shale & Shells	1025	1557
Shale & Lime	1557	1860
Lime	1860	2025
Lime & Shale	2025	2100
Shale	2100	2222
Shale & Shells	2222	2640
Lime & Shale	2640	2940
Lime	2940	3150
Lime & Shale	3150	3178
Shale	3178	3271
Lime & Shale	3271	3305
Lime	3305	3556
Shale & Lime	3556	3602
Lime & Shale	3602	3670
Total Depth		3670'


STATE OF OKLAHOMA)
) SS
 COUNTY OF TULSA)

I hereby certify that the above information is true and correct to the best of my knowledge.

W. H. Barclay
 W. H. Barclay, Asst. Gen. Supt.

Subscribed and sworn to before me this 22nd day of August, 1955.

Bette June Howey
 BETTE JUNE HOWEY, Notary Public
 in and for the State of Oklahoma
 My Commission Expires March 21, 1959



RECEIVED
 STATE CORPORATION COMMISSION
 AUG 25 1955
 CONSERVATION DIVISION
 Wichita, Kansas