

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

WELL PLUGGING RECORD

R 21s NORTH T 13W

			*
	24		

Locate well correctly on above Section Plat

Stafford County, Sec. 24 Twp. 21S Rge. 13W (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner Pam-Kar Drilling Co., Inc.
Lease Name Schmalian Well No. 2
Office Address 333 First Nat'l. Bank - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 13 19 54
Application for plugging filed October 6 19 55
Application for plugging approved October 7 19 55
Plugging commenced November 1 19 55
Plugging completed November 9 19 55
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren Horner
Producing formation Depth to top Bottom Total Depth of Well 3573 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	267'	None
				5-1/2"	3573'	2874'
				Hole was plugged back to 3408' and casing perforated from 3356' to 3366'.		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled the hole with sand from 3408' to 3345' and ran 5 sacks of cement which filled to 3290'. Mudded the hole to 250', set a 10' rock bridge and ran 20 sacks of cement. Mudded the hole to 40', set a 10' rock bridge and ran 10 sacks of cement on top. Plugging completed.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas


STATE OF Kansas, COUNTY OF Sedgwick, ss.
I, Ralph B. McLaughlin (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Ralph B. McLaughlin*
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of November, 19 55

My commission expires December 31, 1958

Donna L. Riley
Donna L. Riley, Notary Public.
STATE CORPORATION COMMISSION



STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS

11-30-1955

Pam-Kar Drilling Co., Inc.

Wichita, Kansas

Well: Schmalian # 2

NE NE NE

Commenced RD 2-7-54
Completed RD 2-17-54Sec. 24-21-13W
Stafford County

Total Depth 3573'

Elevation: 1874 KB

Casing: 267 1/2' 8 5/8" OD 24# Rnd thd 250 Sks. Cement
3573' 5 1/2" OD 14# Rnd thd 100 Sks. Cement

Contractor: Pam-Kar

STRATA	DEPTH		TOPS
Sand & gravel	155	Heebner	3141-1267
Sandy Shale	237	Toronto	3161-1287
Red Bed & shale	701	Brown Lime	3266-1392
Chalk	706	Lansing	3283-1409
Anhydrite	741	Simpson	3525-1651
Shale & shells	1190	Arbuckle	3571-1697
Salt & shale	1300		
Shale	1535		
Broken Lime	2110		
Lime & Shale	2395		
Shale & Lime	2560		
Lime & Shale	2680		
Shale & Lime	3014		
Lime & shale	3575		
Total Depth	3573		

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

PAM-KAR DRILLING COMPANY, INC.
BY

Ralph B. McLaughlin

Signed and sworn to in my presence this 3rd day of March, 1954, by Ralph B. McLaughlin, Secretary of the Pam-Kar Drilling Company, Inc., a corporation in the State of Kansas.

Notary Public

My commission expires Sept. 4, 1957.

PLUGGING
REL. SEC 24 121 R 13w
BOOK PAGE 6 LINE 29