

R

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

3-29-1976

RECEIVED  
STATE CORPORATION COMMISSION

MAR 29 1976

J. Lewis Brock  
Administrator  
245 North Market  
Wichita, Kansas 67202

API Number 15-185-20095-0000 (of this well)  
Wichita, Kansas

Operator's Full Name Jay C Boyer

Complete Address Box 511 Hays, KS

Lease Name Davis Well No. 1

Location SE/NW/NE Sec. 3 Twp. 21 Rge. 14 (E) (W)

County Stafford Total Depth 3685

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Co

Address Box 405 Chase, KS License No. 624

Operation Completed: Hour 1:00 PM Day 26 Month 3 Year 1976

The above well was plugged as follows:

315 ft 8 5/8 surface cement circulated. 3684 ft 5 1/2 long string  
cemented with 100 sacks. Top perf. 3454 ft. Sand to 3400 ft, 5  
sacks cement with bailer. Pulled 370 ft 5 1/2. Pump 2 sacks hulls,  
10 sacks gel, 100 sacks cement to surface.  
Pumped by Allied Cementing Great Bend, KS

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3-29-76

INV. NO. 2970-W

Signed: [Signature]  
Well Plugging Supervisor