

15.185.12199.0001

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 30 1965

CONSERVATION DIVISION  
Wichita, Kansas

8-30-1965

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name G. M. W., Inc.

Complete Address: Box 510, El Dorado, Kansas

Lease Name Davis Well No. # 1

Location SW SW SE Sec. 3 Twp. 21 Rge. 14 (E) (W)

County Stafford Total Depth 3585'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 4:00 PM Day 27th Month August Year 1965

The Above well was plugged as follows:

No record of surface pipe. 3585' of 5 1/2" long string, cemented with  
60 sacks. Top perferation 3463'. Bottom of the hole was sanded to 3450',  
and cemented with 5 sacks. 2220' of 5 1/2" long string was recovered from  
the hole. Hole was flowing with water and a squeeze job was necessary.  
10 sacks of Gel-Mud and 80 sacks of cement was pumped into the surface  
pipe, through an 8 5/8" swage, to a pressure of 250 lbs. A wiping  
plug was run between the mud and the cement.

This cementing was done by Globe Cementing Company.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving  
Well Plugging Supervisor

INVOICED

DATE 8/30/65

INV. NO. 1714-W