

KANSAS

Form CP-3
Rev. 6-4-68STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTJ. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217RECEIVED
STATE CORPORATION COMMISSION
MAR 5 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Kewanee Oil Co.

Complete Address Box 2093 Wichita, KS

Lease Name Morrison Well No. 10

Location C NE/SE/SW Sec. 1 Twp. 21 Rge. 14 (E) W

County Stafford Total Depth 4030

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Co Inc

Address Box 364 Great Bend, KS License No. 399

Operation Completed: Hour 10:00 AM Day 4 Month 3 Year 1974

The above well was plugged as follows:

287 ft 8 5/8 surface cemented with 275 sacks. 3720 ft 5 1/2 long string
cemented with 135 sacks. Top perf. 3376 ft. Sand to 3350 ft, 5 sacks
cement with bailer. Pulled 2837 ft 5 1/2. Pumped 2 sacks hulls, 20 sacks
gel, 100 sacks cement to surface.

Pumped by Halliburton Cementing Co Great Bend, KS

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 3/5/74
INV. NO. 8695-43Signed: [Signature]
Well Plugging Supervisor