

15.185.10757.0001

Form CP-3
Rev. 6-26-62

KS
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 5 1965

CONSERVATION DIVISION
Wichita, Kansas

4-5-1965

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Kewanee Oil Company

Complete Address: Box 2093, Wichita, Kansas

Lease Name Morrison Well No. # 4

Location SE NW SW Sec. 1 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 4127'

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated: _____

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 5:00PM Day 2nd Month April Year 1965

The Above well was plugged as follows:

280' of 8 5/8" surface pipe, cemented with 250 sacks. 3832' of 5 1/2" long
string, cemented with 200 sacks. This is an open hole. 2" plastic tubing
is in the hole from TD to 1663'. Hole was sanded from 1663' to 1643', and
cemented with 5 sacks. 506' of 5 1/2" long string was recovered from the hole.
Hole was flowing with water and a squeeze job was necessary. 20 sacks of
Gel-Mud and 85 sacks of Posmix cement was pumped in surface pipe, through
an 8 5/8" swage, to a pressure of 400 lbs. A wiping plug was run between
the mud and the cement. This cementing was done by Halliburton Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 4/5/65

INV. NO. 925-W