

10
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 23 1965

CONSERVATION DIVISION
Wichita, Kansas

2-23-1965

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Alpine Oil & Royalty Company

Complete Address: 800 Bitting Bldg., Wichita, Kansas

Lease Name Morrison Well No. # 2-A

Location SW NE NE Sec. 1 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3585'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Gabbert-Jones Inc.

Address: 514 Orpheum Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 6:15PM Day 20th Month Feb. Year 1965

The Above well was plugged as follows:

287' of 8 5/8" surface pipe, cement circulated with 300 sacks. Fluid
level in the hole was at 10'. 1st cementing plug and 1/4 sack of hulls
was pushed in fluid to 260', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing plug,
bridged solid with dry cement and hulls on fluid at 40', and cemented
with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 2/24/65

INV. NO. 723-11

Signed: Archie Elving
Well Plugging Supervisor