

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 134-39

LOCATION NW-SE-NW

SEC. 24 TWP. 21 RGE. 13 W

Dry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 2 Lease Bertha Hall

Operator Midstates Oil Corp. Address 7th floor Midstates Bldg. Tulsa, Okla.

Field \_\_\_\_\_ County Stafford

Total Depth 3670 Feet.

Plugging Contractor West Supply Co. Inc.

Plugging Contractor's License No. 14

Address Chase, Kansas

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 5/8" O 298' c.w.c. 5 1/2" set 3669'  
w/ 150 sv cem. Top perf 3621 Sanded hole to  
3610' dumped 5 sv cem. Shut off and pulled  
5 1/2" casing. Mudded hole to 280' set rock  
bridge and dumped 20 sv cem. Mud to  
35' rock bridge and 10 sv cem. to base  
of cellar

Warren L. Harner  
District Conservation Agent

Date Aug 14, 1955

**PLUGGING**  
BOOK SEC. 24 TWP. 21 R. 13 W.  
PAGE 134 LINE 39

**RECEIVED**  
STATE CORPORATION COMMISSION

AUG 16 1955

CONSERVATION DIVISION  
Wichita, Kansas

8-16-1955