

Y
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Circle Oil Company, Inc.

Complete Address: 816 Bitting Bldg., Wichita, Kansas

Lease Name Hickman Well No. # 1

Location NW SW NE Sec. 24 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3721'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Sage Drilling Company, Inc.

Address: 816 Bitting Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 3:30 PM Day 24th Month June Year 1965

The Above well was plugged as follows:

273' of 8 5/8" surface pipe, cement circulated with 300 sacks. Fluid
level in the hole was at 95'. 1st cementing plug and 1/4 sack of hulls
was pushed in fluid to 260', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with dry cement and hulls on fluid at 40', and
cemented with 10 sacks to the base of the cellar. Rat hole bridged
and cemented with 2 sacks.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED

JUN 28 1965

Signed: *Archie Elving*
Well Plugging Supervisor

DATE 6/28/65

CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 1344-W