

WELL LOG - KEELEY #1

WELL OWNER: Tom Palmer

Location: NE NE NW
Section 5-21S-14W
Stafford County, Kansas
Elevation: 1924 R. B.

CONTRACTOR: The Palmer Oil Corporation

Commenced: 12/29/50

Completed: 1/10/51

RESULTS: Dry Hole

Casing Record

8 5/8" - 862' cemented 458 sacks

Sand & shale	0	130
Shale & shells	130	270
Sand	270	329
Shale	329	459
Sand & shale	459	518
Shale	518	627
Shale & shells	627	837
Shale	837	850
Anhydrite	850	870
Shale & shells	870	2034
Lime & shale	2034	2962
Lime	2962	3228
Lime & shale	3228	3300
Lime	3300	3630 T. D.

Formation Tops (R. B.)

All tops corrected to Schlumberger Log.

Heebner	3208
Brown Lime	3310
Lansing	3318
Base K. C.	3522
Cherty Lime	3576
Simpson	3586
Arbuckle	3617

$$\begin{array}{r} 3576 \\ - 1924 \\ \hline 1652 \end{array}$$

$$\begin{array}{r} 3617 \\ - 1924 \\ \hline 1693 \end{array}$$

Drill Stem Test 3619-3630. Packer set at 3619 - tool open 30 minutes - recovered 300' salt water.

This is to certify that the above is a true and correct log, according to the daily drilling reports.

THE PALMER OIL CORPORATION

By A. H. Smith

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

Subscribed and sworn to before me, a Notary Public in said county and state this 31st day of January, 1951.

Olaf M. Kelling
Notary Public

My commission expires: 9/30/53.

RECEIVED
STATE CORPORATION
FEB - 1 1951
CONSERVATION DIVISION
Wichita, Kansas

ALL RIGHTS RESERVED
FEB 28 5 21-8-14
1951