

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Return to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH

Section Plat grid with 4 columns and 4 rows.

Locate well correctly on above Section Plat

Stafford County. Sec. 5 Twp. 21S Rge. 14 (E) W (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines 280' W.L. & 410' S.L.
Lease Owner The Vickers Petroleum Co., Inc. & Jayhawk Drilling Co., Inc.
Lease Name Keeley Well No. 1
Office Address 201 W-K-H Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed January 25, 19 51
Application for plugging filed January 25, 19 51
Application for plugging approved January 25, 19 51
Plugging commenced January 25, 19 51
Plugging completed January 25, 19 51
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough, Great Bend, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3729 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: 8 5/8", 870', None.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug @ 250' Dumped 15 sx. cement Filled w/mud to 30'
Set plug @ 30' Dumped 10 sx. cement for cap.

RECEIVED
STATE CORPORATION COMMISSION
JAN 31 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to The Vickers Petroleum Co., Inc.
Address 201 W-K-H Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
John M. Little (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John M. Little
201 W-K-H Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 26 day of January, 19 51

Allen Denton Notary Public

My commission expires August 13, 1953.

PLUGGING
FILE SEC 5-21 R 146
BOOK PAGE 58 LINE 18

THE VICKERS PETROLEUM CO., INC.
AND
JAYHAWK DRILLING CO., INC.

15.185.12256.0000

Keeley, Well #1
280' W.L. 410' S.L. Sec. 5-21S-14W
Stafford County, Kansas

Casing Record:
8 5/8" @ 870' w/400 sx.

Commenced : January 12, 1951
Completed : January 25, 1951

Elevation 1928 R.B.
D & A

LOG

Surface Sand & Soil	0-280	Lime	3055-3165
Shale	280-310	Lime & Shale	3165-3284
Sand	310-400	Shale	3284-3358
Red Bed & Sand	400-700	Lime & Shale	3358-3624
Red Bed, Shale & Shells	700-868	Chert	3624-3661
Anhydrite	868-895	Shale	3661-3673
Red Bed, Shale & Shells	895-1370	Sand	3673-3678
Salt, Shale & Shells	1370-1435	Shale	3678-3703
Salt & Shale	1435-1610	Dolomite	3703-3729 TD.
Lime & Shale	1610-1755		
Broken Lime	1755-1980	DST 3702½' to 3710'	
Broken Lime & Sand	1980-1990	Weakblow, Died in 14 min.	
Sand	1990-2020	Open 20 min. Recovered 90' Drlg. Mud	
Broken Lime	2020-2120	B. H. P. 330#	
Lime & Shale	2120-3055		
		DST 3707' to 3719'	
		Good blow open ½ hr. Recovered 90'	
		Salt water B.H.P. 50#	

TOPS:

Heebner	3254'
Douglas	3284'
Brown Lime	3358'
Lansing	3368'
Viola	3624'
Simpson	3661'
Arbuckle	3703'

RECEIVED
STATE DEPARTMENT OF COMMISSION
JAN 31 1951
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this log is true and correct to the best of my knowledge and belief.

THE VICKERS PETROLEUM CO., INC.

BY: *N.P. Simmons*

Sworn and subscribed to before me this 30th day of January, 1951.

Allen P. Denton
Notary Public

My commission expires Aug. 13, 1953.

PLUGGING
FILE SEC-5 T-21 R-14W
BOOK PAGE-58 LINE-18