

15.185.10771.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER N/A

LEASE NAME BOYD

WELL NUMBER 1

2310 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 5 TWP. 21 SRGE. 14 ~~XXXX~~ (W)

COUNTY Stafford

Date Well Completed 6/17/59

Plugging Commenced 3/25/85

Plugging Completed 4/1/85

LEASE OPERATOR CHAPMAN EXPLORATION, INC.

ADDRESS 404 Cities Service Building

PHONE#(918) - 582-2247 Tulsa, Oklahoma 74119
OPERATORS LICENSE NO. 6939

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? Stafford, Mr. Metz

Is ACO-1 filed? No If not, is well log attached? Log was sent w/application to plug.

Producing Formation LKC Depth to Top 3320' Bottom 3550' T.D. 3625'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC	Oil	3320	3500	8-5/8"	250'	None
Arbuckle	Water	3617	3625	5-1/2"	3613'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mixed 2 sks hulls, 50 sks 60/40 poz and pump down 5 1/2". Then mix 1 sk hulls, 20 sks gel and 100 sks cement and pump down 5 1/2". Shut in on vacuum. Pumped down 8-5/8" annulus with 2 1/2 sks hulls and 150 sks cement. Max. Pres. 300#. SI Pres. 150#. On 4/1/85 dump 6 yds. ready-mix concrete down 5 1/2".

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SUN CEMENTERS License No. _____

Address Great Bend, Kansas

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

VIRGIL L. JOHNSON (Employee of Operator) ~~or Operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED

STATE CORPORATION COMMISSION

(Signature) [Signature]

(Address) Virgil L. Johnson

404 Cities Service Building

Tulsa, Oklahoma 74119

SUBSCRIBED AND SWORN TO before me this 2nd day of April, 19 85

APR 4 1985
CONSULTING DIVISION
Wichita, Kansas

[Signature]
Notary Public

My Commission Expires: JUNE 7, 1988