

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.--82-3-117

API NUMBER 15-185-10835-0000

LEASE NAME McGinty

WELL NUMBER #1

 Ft. from S Section Line

 Ft. from E Section Line
 NE NE NW

SEC. 34 TWP. 21 RGE 14W (E) or (W) (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 8-17-87

Plugging Completed 8-21-87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Carl Boxberger Oil, Inc.

ADDRESS Box 474
Great Bend, Kansas 67530

PHONE # (316) 792-0716 OPERATORS LICENSE NO. 4707

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3774'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	240'	none
				5-1/2"	3773'	273'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 3250' and 5 sacks cement. Well parted @273', laid down 273' of 5-1/2" casing. Tied onto 8-5/8" surface and pumped 20 sacks econolite with 200# hulls, followed with 130 sacks econolite with 200# hulls. Max. press. 200#, shut in 0#. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 25th day of August, 1987

Jane Hoover
 Notary Public

My Commission Expires:



8-26-1987
AUG 25 1987 Form CP-4
 Revised 07-86

Wichita, Kansas

15-185-10835-0000

MAX COHEN

#1

McGINTY

34-21-14W

NE NE NW

Contr.

STAFFORD

County

E 1940

Comm.

Comp.

4-6-51

IP


1585 BOPD

DRAW DOWN

Tops	Depth	Datum
LANS	3400	-1460
V10	3676	-1736
SIMP	3718	-1778
ARB	3764	-1824
T.D.	3774	-1834

Casing
 8" 246 PERF 3528-30,
 5" 3773 3000' OIH
 SWB & FLOW 50
 BOPH

HICKMAN POOL



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

STATE OF KANSAS

JUL 31 1987

WICHITA, KANSAS