


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above
Section Flat

Stafford County, Sec. 34 Twp. 21S Rge. (E) 14 (W)
Location as "NE/CNW/SW" or footage from lines NW SW SW
Lease Owner Circle Oil Company, Inc.
Lease Name Schartz Well No. 1
Office Address 500 Bitting Bldg., Wichita, Ks. 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 21, 19 73
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced February 21, 19 73
Plugging completed February 21, 19 73
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Russell Biberstein of Attica)

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3825 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|------|--------|--------|------------|
| | Surface | 0 | 246' | 8-5/8" | 246' | None |
| | Casing | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 450 Feet,
40 sax Cement; Mud to 200 Feet, 25 sax
Cement; Mud to 40 Feet, 1/2 sax Hulls,
Plug and 15 sax Cement to Base of Cellar;
2 sax Cement in Rat Hole.

RECEIVED
STATE CORPORATION COMMISSION
MAR 1 1973
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Allied Cementing Co.
Address Box 207, Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Clarence Michael of Sage Drilling Co. (employee of owner) or (owner or operator) of the above described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clarence Michael
500 Bitting Bldg., Wichita, Kansas
(Address)

Subscribed and sworn to before me this 26th day of February, 19 73



Louise K. Whitted
Notary Public.

My commission expires November 26, 1974.

DRILLERS LOG

SCHARTZ NO. 1

| | | |
|-----------------------------------|-------------------------------------|--|
| CASING RECORD: | OPERATOR: Circle Oil Company, Inc. | DESCRIPTION: |
| 8-5/8" @ 246' w/200 sax cement | CONTRACTOR: Sage Drilling Co., Inc. | NW SW SW Sec. 34-21S-14W Stafford Co., Ks. |
| TOTAL DEPTH: 3825' | COMMENCED: February 13, 1973 | ELEVATION: 1944KB |
| | COMPLETED: February 21, 1973 | |

| <u>FORMATION</u> | <u>FROM</u> | <u>TO</u> | <u>REMARKS</u> |
|------------------|-------------|-----------|----------------|
| Sand & Shale | 0 | 250 | |
| Shale & Red Bed | 250 | 864 | |
| Anhydrite | 864 | 885 | |
| Shale & Shells | 885 | 1240 | |
| Shale | 1240 | 2037 | |
| Lime & Shale | 2037 | 2200 | |
| Shale | 2200 | 2425 | |
| Shale & Lime | 2425 | 2690 | |
| Lime & Shale | 2690 | 3440 | |
| Lime | 3440 | 3525 | |
| Lime & Shale | 3525 | 3600 | |
| Lime | 3600 | 3825 | D&A |


RECEIVED
 STATE CORPORATION COMMISSION
 MAR 1 1973
 CONSERVATION DIVISION
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Clarence Michael
Clarence Michael

Subscribed and sworn to before me this 26th day of February, 1973.



Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1974.