

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 36 Twp. 21S Rge. (X) 14(W)

Location as "NE/CNW/SW" or footage from lines NE SE SW
Lease Owner John C. Graves & Lee Phillips Oil Company
Lease Name McGinty Well No. 1
Office Address 412 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 24, 19 65
Application for plugging filed October 24, 19 65
Application for plugging approved October 24, 19 65
Plugging commenced October 24, 19 65
Plugging completed October 24, 19 65
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3307 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 260 feet. Followed by wooden plug and 1/4 sack hulls. Placed 25 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/4 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graves Drilling Co., Inc.
Address 412 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, ss.
John C. Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *John C. Graves*
412 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of October, 19 65

My commission expires April 30, 1967

Betty Brandt
Betty Brandt Notary Public.

ROTARY DRILLERS' LOG

OPERATOR: John C. Graves and
Lee Phillips Oil Company
412 Union Center
Wichita, Kansas

DRILLING COMMENCED: October 20, 1965

CONTRACTOR: Graves Drilling Co., Inc.
412 Union Center
Wichita, Kansas

DRILLING COMPLETED: October 24, 1965

CASING RECORD: 10 Jts. 320' 8-5/8"
cemented with 350 sacks

LOCATION: McGinty No. 1
NE SE SW
Section 36-21S-14W
Stafford County, Kansas

0 - 319	Shale with lime shells
319 - 814	Shale, shells & red bed
814 - 839	Anhydrite
839 - 1625	Shale & shells
1625 - 2380	Lime & shale
2380 - 2705	Shale & lime
2705 - 3307	Lime & shale
3307	Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC. **RECEIVED**
STATE CORPORATION COMMISSION
By John C. Graves **OCT 28 1965**
President
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS:
BUTLER COUNTY)

Subscribed and sworn to before me, a Notary Public, this 27th of October, 1965

My commission expires:
April 30, 1967

Betty Brandt
Betty Brandt Notary Public