


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Stafford County, Sec. 36 Twp. 21S Rge. 14 (X) (W)

Location as "NE/CNW/SW" or footage from lines C S/2 NE NE  
Lease Owner Bowers Drilling Company, Inc.  
Lease Name McGinty Well No. 1  
Office Address 416 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 31 19 63  
Application for plugging filed October 30 19 63  
Application for plugging approved October 30 19 63  
Plugging commenced October 31 19 63  
Plugging completed October 31 19 63  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, verbally

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 3770 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	313	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 275'  
Set first plug at 275' with 25 sax cement, 1/4 sax hulls  
Filled with heavy mud to 40'  
Set second plug at 40' with 10 sax cement, 1/4 sax hulls

RECEIVED  
STATE CORPORATION COMMISSION

NOV 12 1963

11-12-1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Bowers Drilling Company, Inc.  
Address 416 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
(employee-of-owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bauer  
416 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of November, 19 63

Anna J. Miller  
Notary Public.

My commission expires May 1, 1966



WELL LOG

COMPANY: Bowers Drilling Company, Inc.  
 CONTRACTOR: Bowers Drilling Company, Inc.  
 FARM: McGinty #1  
 LOCATION: C S/2 NE NE Section 36-21S-14W  
 Stafford County, Kansas

COMMENCED: October 21, 1963  
 COMPLETED: October 31, 1963  
 ELEVATION: 1921 Derrick Floor

0 - 100	Sand
100 - 248	Sand, Blue Shale
248 - 314	Sand and Shale
314 - 668	Redbed
668 - 814	Redbed, shale and shells
814 - 836	Anhydrite
836 - 1363	Shale shales
1363 - 3410	Lime and shale
3410 - 3469	Lime
3469 - 3540	Lime and shale
3540 - 3595	Lime
3595 - 3770	Lime and Shale
3770	Total Depth

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 12 1963  
 CONSERVATION DIVISION  
 Wichita, Kansas

1921  
 1107

SAMPLE TOPS:

Heebner	3273	Viola	3680
Brown Lime	3400	Simpson	3714
Lansing	3410	Arbuckle	3762
Base K.C.	3638		

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the copy of the log of the McGinty #1, C S/2 NE NE Section 36-21S-14W, Stafford County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

Emil E. Bowers

Subscribed and sworn to before me, a Notary Public in and for Sedgwick County, Kansas, this 7th day of November, 1963.

Donna F. Miller  
 Donna F. Miller, Notary Public

My commission expires May 1, 1966.