

WELL PLUGGING RECORD


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Stafford

County. Sec. 36 Twp. 21 Rge. (E) 14 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW NE  
Lease Owner Barbara Oil Company  
Lease Name Curtis Well No. 1  
Office Address 322 Central Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 2, 1951 19  
Application for plugging filed August 2, 1951 19  
Application for plugging approved August 6, 1951 19  
Plugging commenced August 2, 1951 19  
Plugging completed August 2, 1951 19  
Reason for abandonment of well or producing formation D&A

NORTH



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C.D. Stough, Box 207, Great Bend, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 3830 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 1/2"	203'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole from bottom to within 280' of the top with heavy mud, set plug and cemented with 15 sacks, filled hole up to 30' below cellar and cemented with additional 10 sacks.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 11 1951

8-11-1951

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Barbara Oil Company, Wichita, Kansas  
Address 322 Central Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

R.F. Ramsey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

322 Central Building, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of August, 1951

*Mildred Fisher*  
Notary Public.

My commission expires March 2, 1953

PLUGGING  
FILE SEC 36 T 21 R 14  
BOOK PAGE 100 LINE 33

WELL LOG CURTIS #1

Barbara Oil Company, Lease Owner	Section 36, Twp. 21S, Rge. 14W
Garvey Oil, Contractor	Location: SW SW NE
Rotary Total Depth: 3830'	County: Stafford, Kansas
Commenced: July 23, 1951	Casing: 221' of 8 5/8" w/175 sax
Completed: August 2, 1951	Elevation: 1927 R.B.
Production: D & A	

All figures below indicate bottom of formation:

40	Surface Clay		
175	Sand		
190	Shale & Sand		
203	Lime & Shale	Heebner:	3289
820	Shale & Red Bed	Brown Lime:	3408
850	Anhydrite	Lansing:	3419
1759	Shale & Shells	B. K. C.	3648
2600	Lime & Shale	Conglomerate	3679
2840	Shale & Shells	Viola:	3704
2880	Shale & Lime	Simpson:	3757
2916	Shale	Arbuckle:	3800
2995	Lime & Shale		
3066	Lime		
3220	Lime & Shale		
3270	Lime		
3365	Lime & Shale		
3433	Shale & Shells		
3490	Lime		
3520	Cherty Lime		
3683	Lime		
3761	Lime & Shale		
3805	Simpson		
3830	Lime		
3830'	R.T.D.		

I hereby certify that this is a true and correct log of the above mentioned well.

PLUGGING GARVEY OIL  
 TWP. SEC. 36, T. 21S, R. 14W  
 BOOK PAGE 10 AMB 53  
 RECEIVED  
 STATE CORPORATION

STATE OF KANSAS )  
COUNTY OF SEDGWICK )

SS. Eric H. Jager

Subscribed to and sworn to before me, Notary Public, in said County and State, this 4th day of August, 1951.

My commission expires: 10-13-54

*Charlotte Weidman*  
Notary Public