


Give All Information Completely  
Map Required Affidavit  
Map Deliver Report to  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. \_\_\_\_\_ Twp. \_\_\_\_\_ Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W)  
Location as "NE/CNW/SW" or footage from lines \_\_\_\_\_  
Lease Owner Shawver-Armour  
Lease Name McGinty Well No. 1  
Office Address 817 Central Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed July 12, 1954 19\_\_\_\_  
Application for plugging filed 8-26-55 19\_\_\_\_  
Application for plugging approved 8-26-55 19\_\_\_\_  
Plugging commenced 8-26-55 19\_\_\_\_  
Plugging completed 9-2-55 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production Aug. 23 1955  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Red Horner  
Producing formation Arbuckle Depth to top 3747 Bottom 3751 Total Depth of Well 3751 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	209	8-5/8	209	None
Arbuckle		0	3748	5-1/2	3748	2010

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

3606 - 3400' Plugged back w/ crushed rock  
3400 Dumped 5 sx cement w/ dump bailer  
3370 Top of cement  
3370 - 225 Filled Hole with mud  
225 Set rock bridge, cumped 20 sx cement.  
160 top of cement  
160 - 35 filled w/ mud  
35' Set rock bridge - dumped 10 sx cement for cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J & M Casing Pulling Company  
Address Box 711, Great Bend, Kansas

9-8-1955

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
James Armour (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Armour

817 Central Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 7 day of September 1955

My commission expires Mar 30, 1957

Rosemary Penrose  
Rosemary Penrose Notary Public.

PLUGGING  
FILE SEC 36 T 21 R 14 W  
BOOK PAGE 46 LINE 16


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company K & E DRILLING, INC.  
Farm-McGinty No. 1

SEC. 36 T. 21 R.14W  
SE SE SW

Total Depth. 3751  
Comm. 6-28-54 Comp. 7-9-54  
Shot or Treated.  
Contractor.  
Issued. 9-25-54

County Stafford  
KANSAS



Elevation. 1923

Production. 238 BO, tr water

CASING:

8 5/8 @ 209' w/ 135 sx cmt.  
5 1/2 @ 3748' w/ 100 sx cmt.

Figures Indicate Bottom of Formations.

sand & soil	190
sand & shale	209
sand, shale & red bed	585
shale & shells	1765
lime & shale	3210
lime	3270
lime & shale	3410
lime	3460
lime & shale	3490
lime	3638
shale & lime	3751
Total Depth	

SCOUT TOPS:

Lansing	3412
Viola	3670
Simpson	3702
Arbuckle	3746

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 30 1955  
CONSERVATION DIVISION  
Wichita, Kansas

**PLUGGING**  
FILE SEC 36 T 21 R 14 W  
BOOK PAGE 146 LINE 16