

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Stafford County, Sec. 36 Twp. 21S Rge. 14W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW SW

Lease Owner Welch & Olsson Drilling Co. Inc.

Lease Name McGinty Well No. 1

Office Address 1017 Union National Bank Bldg., Wichita, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed 8-28 1953

Application for plugging filed 8-28 1953

Application for plugging approved 8-28 1953


Plugging commenced 8-28- 1953

Plugging completed 8-28 1953

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 148, Pratt, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3815' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	330'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded to 270' and set wooden plug. Cemented and displaced 20 sacks cement through drill pipe onto plug. Mudded to 40' and set second plug, filled hole to bottom of well cellar with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Welch & Olsson Drilling Co. Inc.

Address _____

STATE OF Kansas, COUNTY OF Sedgwick, ss.

R. E. Welch (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Handwritten Signature]

(Address) _____

SUBSCRIBED AND SWORN to before me this 2nd day of September, 1953

Marcella J. Rives
Notary Public.

My commission expires Feb. 27, 1956
STATE OF KANSAS 24-7368-5 3-53-20M

027-3-53
CONSERVATION DIVISION

PLUGGING
FILE NO. 26-12-14u
BOOK PAGE 125 LINE 34

10-3-1953

WELL LOG

WELCH & OLSSON DRILLING CO. INC.,

Elevation: 1933' R. B.

CONTRACTOR: Welch & Olsson Drilling Co. Inc.

Commenced Drlg: 8-18-53

McGinty No. 1,
NW NW SW Sec. 36-21S-14W,
Stafford County, Kansas.

Completed Drlg: 8-28-53

Production: D & A

Casing record:

Set 330' of 8 5/8" with 225 sacks cement.

(Figures indicate bottom of formations)

<u>FORMATIONS:</u>	<u>DEPTHS</u>	<u>FORMATION TOPS</u>
Surface soil	260'	Heebner 3289' - 1356'
Sand & Shale Streaks	315'	Toronto 3309' - 1376'
Shale	325'	Brown Lime 3411' - 1478'
Red Bed-sandy	385'	Lansing K. C. 3420' - 1487'
Red Bed	820'	Base K. C. 3642' - 1609'
Anyhdrite	845'	Conglomerate 3684' - 1751'
Shale & Shells	1700'	Viola 3687' - 1754'
Lime	1825'	Simpson Shale 3732' - 1799'
Lime & Shale	1900'	Arbuckle 3775' - 1842'
Lime	1965'	
Lime & Shale	2365'	
Shale & Shell	2915'	
Lime & Shale	3180'	
Lime	3289'	
Heebner	3295'	
Lime	3300'	
Lime & Shale	3380'	
Lime	3690'	
Chert	3762'	
Shale	3775'	
Lime	3815' T. D.	

STATE OF KANSAS,
COUNTY OF SEDGWICK, SS:

I Hereby certify that the above is a true and correct copy of Drillers Log of Well drilled in the NW NW SW of Sec. 36-21S-14W, Stafford County, Kansas.

WELCH & OLSSON DRILLING COMPANY, INC.,

BY: *R. E. Welch*

R. E. Welch

Subscribed and sworn to before me this 2nd day of September, 1953.

My Commission Expires: Feb. 27, 1956.

Marcella H. Davis
Notary PublicRECEIVED
STATE COMMISSION
SEP 13 1953
DIVISION
KANSASPLUGGING
WELL SEC 36 T 21 R 14W
BOOK PAGE 125 LINE 34