


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County. Sec. 36 Twp. 21 Rge. 11 (E) 11 (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines C. NW SE NE
Lease Owner Pickrell Drilling Company
Lease Name Curtis #1 Well No. 1
Office Address 705 4th Nat'l. Bank Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8/5.1952
Application for plugging filed 8/5.1952
Application for plugging approved 8/5.1952
Plugging commenced 8/5.1952
Plugging completed 8/5.1952
Reason for abandonment of well or producing formation D & A

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19...
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well 3763 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	330'	None
				5 1/2"	3768'	2930'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from... feet to... feet for each plug set.

Hole was plugged back from 3763' with crushed rock and 5 sacks cement.
Shot casing off at 2930' - pulled casing out of hole and Globe Oilwell Cementing Co. squeezed 85 sacks cement and 15 sacks mud. Let set four days - broke off cementing head and put in 5 sacks cement.

Name of Plugging Contractor Forbes Casing Pulling Co.
Address Box 221
Great Bend, Kansas

STATE CORPORATION COMMISSION
AUG 23 1952
8-23-1952
CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
C. W. Sebitts (employer or owner or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

705 4th Nat'l. Bank Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of August, 1952.

My commission expires Mar. 22, 1956

My commission expires [Signature] Notary Public.

PLUGGING
FILE 23-36-21-114W
BOOK PAGE 34 LINE 43

ROTARY DRILLING LOG

COMPANY: Pickrell Drlg. Company etal
 Wichita, Kansas
 Rotary Drilling Commenced 7-3-52
 Rotary Drilling Completed 7-11-52

LOCATION: Curtis #1
 NW SE NE 36-21S-14W
 Stafford County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY
 Wichita, Kansas

CASING RECORD: 330' of 5 8/5" 24# smls. casing set at 330', in a 12 1/4" hole, cemented with 200 sacks cement. cement circulated.

3768.49' of 5 1/2" 11# J-55 smls. casing set at 3762' in a 7 7/8" hole, cemented with 125 sacks cement.

LOG

(Figures indicate bottom of formation - measurements from top of rotary bushing.)

Sand	160	Circulate for samples at	3450'
Shale & sand	185	" " " "	3478'
Sand	295	" " " "	3486'
Shale & sand	330	" " " "	3529'
Sand	340	" " " "	3550'
Red bed & shale	685	" " " "	3575'
Red bed & shale	815	" " " "	3606'
Anhydrite	840	" " " "	3689'
Red bed, shale & shells	900	" " " "	3727'
Shale & shells	1205	" " " "	3752'
Shale salt	1620	" " " "	3762'
Shale & shells	1660		
Lime & shale	1840		
Lime & shale	1905	Slope test at 2000' - 0° off.	
Shale lime	2175		
Shale & lime	2315		
Lime & shale	2340		
Shale, stickey	2370		
Lime & shale	2690		
Shale & lime	2826		
Lime & shale	2940		
Lime	3067		
Lime	3661		
Viola chert	3689		
Cherty Viola & Simpson shale	3727		
Lime	3742		
Conglomerate	3759		
Arbuckle	3762	RTD	

PLUGGING
 FILE SEC 36 T 21 R 14W
 BOOK PAGE 34 LINE 43

RECEIVED
 CONSERVATION COMMISSION
 AUG 23 1952
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
 By C. W. Sebitts
 Attorney-in-Fact

STATE OF KANSAS, }
 COUNTY OF SEDGWICK } ss.:

On this 18th day of August, 19 52, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: Mar. 22, 1956

Celeste D. Rasmussen
 Notary Public