

STATE OF KANSAS
STATE CORPORATION COMMISSION
220 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-10791-0001

LEASE NAME Morrison #2 SWD

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER _____

SPOT LOCATION NW NE SW

SEC. 21 TWP. 21 RGE. 14 (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 9/18/84

Plugging Completed 9/18/84

LEASE OPERATOR D.R. Lauck
ADDRESS 221 S. Broadway, Suite 400, Wichita, Ks. 67202

PHONE # (316) 263-8267 OPERATORS LICENSE NO. 5427

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3835'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	868'	none
				5 1/2"	3805'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plug job only - No pipe recovery. Pumped 250 sacks 60/40 poz 3% gel 3% c.c. down 5 1/2" casing & 150 sacks 60/40 poz 3% gel 3% c.c. down surface pipe.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 2nd day of October, 1984

My Commission expires:



RECEIVED
STATE OF KANSAS COMMISSION
Notary Public

OCT 04 1984

CONSERVATION DIVISION
Wichita, Kansas

Form CP-4 1-84
Revised 06-83

15.185.10791.0000

D. R. Lauck Oil Company, Inc.
and Sunray Mid-Continent Oil Company

Morrison #2
NW NE SW Sec. 21-21S-14W
Stafford County, Kansas

Commenced: July 31, 1956
Completed: August 10, 1956

Contractor: Lauck Drilling Company, Inc.

Casing: 850' 8-5/8" cemented with 425 sacks.
3805' 5-1/2" cemented with 125 sacks.

Elevation: GR 1938; DF 1941; KB 1943.

Drillers Log

Sand & clay	230
Blue shale & clay	310
Dakota sand	390
Red Bed & Shale	650
Shale & Shells	725
Shale & Red Bed	850
Red Bed	860
Anhydrite	890
Red Bed; Shale & Shells	1320
Salt & Shale	1420
Shale & Shells	1735
Lime & Shale	1925
Lime	2025
Lime & Shale	2730
Shale & Shells	2785
Lime	2840
Lime & Shale	3080
Lime	3292
Heebner Shale	3295
Lime	3308
Shale (Douglas)	3410
Lime	3685
Chert (Viola)	3710
Chert & Lime	3757
Sand	3760
Shale (Simpson)	3785
Lime	3805
Rotary Total Depth	3805

Tops

	<u>Sample</u>	<u>Halliburton</u>
Heebner	3291-1348	3292-1349
Douglas	3333-1390	3334-1391
Brown Lime	3410-1467	3411-1468
Lansing/KC	3419-1476	3420-1477
Base K.C.	3653-1710	3655-1712
Conglomerate	3685-1742	3688-1745
Viola	3698-1755	3699-1756
Simpson Shale	3730-1787	3731-1788
Simpson Sand	3756-1813	3757-1814
Arbuckle	3785-1842	3786-1843
Rotary Total Depth	3805-1862	3806-1863

DST #1 (W) 3532-3570 open 30 min. weak
blow 5 min. Recovered 15' mud.
FFP 0#, BHP 800# in 20 min.

DST #2 (W) 3701-3710 open 30 min. weak
blow 5 min. Recovered 10' mud.
FFP 0#, BHP 0# in 20 min.

DST #3 (W) 3757-3760 (3758-3761 Halliburton)
open 1 hr, strong blow 1 hour.
Recovered 540' gas and 1200' fluid,
est. 700' clean gassy oil, 500'
water. IFP 110#, FFP 510#, BHP
790# in 30 min.

RECEIVED
STATE COMMISSION

JAN 21 1983

OBSERVATION DIVISION
Wichita, Kansas