



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 14 1964

CONSERVATION DIVISION
Wichita, Kansas

2-14-1964

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Marty Hayes of Alpine Oil & Royalty Co. has this date requested permission to plug the following described well:

Mr. Hayes guarantees payment of the plugging fee.

Operator's full Name: Alpine Oil & Royalty Co.

Complete Address: 800 Bitting Bldg., Wichita, Kansas

Lease Name: Morrison "B" Well No. # 3

Location: SW SE SE Sec. 1 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3642 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hayes was instructed to plug the well as follows:

282' of 8 5/8" surface pipe, cemented with 275 sacks. Fill hole with mud to 275', 1st cementing plug, bridged with hulls, and cemented with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridged with hulls, and cemented with 10 sacks to base cellar. Bridge rat & mouse hole and cement with 4 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent