



15.185.30116.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
SEP 3 1965
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Johnnie Crow of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Crow guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name: Hall "Q" Well No. # 1

Location: SE NW SE Sec. 23 Twp. 21 Rge. 13(E) (W) W

County Stafford Total Depth 3685' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Crow was instructed to plug the well as follows:

225' of 8 5/8" surface pipe, cement circulated with 225 sacks.
Fill hole with drilling mud to 210', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling mud
to 40', 2nd cementing plug, bridge with hulls, and cement with 10
sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,
Achie Elving