

State of Kansas



15.185.20571.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

MAR 11 1975

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Zimmerman of Woodman-Iannitti Drlg has this
date requested permission to plug the following described well:Mr. Zimmerman guarantees payment of the plugging fee.Operator's full Name: Brougher Oil IncComplete Address: Drawer 1367 Great Bend, KSLease Name: Wetig Well No. 1Location: SE/NW/NW Sec. 31 Twp. 21s Rge. 13 (E)(W) WCounty: Stafford Total Depth 3772 Oil WellGas Well Input Well SWD Well D & A Lost Hole Mr. Zimmerman was instructed to plug the well as follows:329 ft 8 5/8 surface cemented with 275 sacks. Pump plug,35 sacks cement to 300 ft. Mud to 40 ft, plug, 1/2 sackhulls, 15 sacks cement to surface. 2 sacks cement inrat hole.Pumped by Halliburton Cementing Great Bend, KS

Very truly yours,

Conservation Division Agent