



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 19 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Milt Raymer of Mc Adams Pipe & Supply Co. has this date requested permission to plug the following described well:

Mr. Mc Adams Pipe & Supply guarantees payment of the plugging fee.  
Company

Operator's full Name: Petroleum, Inc.

Complete Address: Box 433, Great Bend, Kansas 67530

Lease Name: Rude Well No. # 1

Location: NE SW NE Sec. 1 Twp. 16 Rge. 13 (E)(W) W

County: Barton Total Depth 3333" Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. John Glenn was instructed to plug the well as follows:

8 5/8" 430' Cwc. Perf. 2920'.

Sanded hole back to 2900' & dumped 4 sax cement with dump bailer.

Pulled pipe. Mud to 320', set 20' rock bridge, & displaced 5 yds.

Ready-mix Cement, cementing from 300' to base of cellar.

Very truly yours,

Don L. ...  
Conservation Division Agent