

State of Kansas



FORM - CP-2  
Rev. 6-26-62

15.185.11335.0000

JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

NOV 1 1963

CONSERVATION DIVISION  
Wichita, Kansas

11-1-1963

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Billy Musgrove of Bowers Drilling Co. has this date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: Bowers Drilling Co.

Complete Address: 416 Union Center, Wichita, Kansas

Lease Name: McGinty Well No. # 1

Location: C S/2 NE SE Sec. 36 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3770 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Musgrove was instructed to plug the well as follows:

314' of 8.5/8" surface pipe, cemented with 450 sacks.  
Fill hole with drilling mud to 275', 1st cementing plug,  
1/2 sack hulls, cement with 25 sacks. Fill hole with drill-  
ing mud to 40', 2nd cementing plug, 1/2 sack hulls, cement  
with 10 sacks to base cellar. Bridge and cement rat hole  
with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent