

15.185.30332.0000

Form GP-3
Rev. 6-26-62

K
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued May 1, 1967.

Operator's Full Name Circle Oil Company, Inc.

Complete Address: 500 Bitting Bldg., Wichita, Kansas 67202

Lease Name Schmalian Well No. # 1

Location NW SW NW Sec. 23 Twp. 21 Rge. 13 (E) (W)W

County Stafford Total Depth 3692'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas 67530 License No. 49

Operation Completed: Hour 1:30PM Day 23rd Month May Year 1967

The Above well was plugged as follows:

265' of 8 5/8" surface pipe, cemented with 235 sacks. 3690' of 5 1/2" long string,
cemented with 150 sacks. Plug back T.D. 3500'. Top perferation 3461'. Bottom
of the hole was sanded to 3400', and cemented with 5 sacks, through the dump
bailer. 2550' of 5 1/2" long string was recovered from the hole. Bridge plug was
pushed in fluid to 260', bridge plug and rock bridge from 260' to 250'. 12
sacks of cement was mixed in a barrel, and put on plug at 250', through the
dump bailer, and let set over-night. Fluid in the hole was bailed dry, and 13
sacks of cement was added to the plug, Hole was filled with mud to 40', rock
bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 5/24/67
INV. NO. 5279-w