

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 29 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Woodman & Iannitti Drilling Company

Complete Address: 706 Union National Bldg., Wichita, Kansas

Lease Name Hall Well No. # 1

Location NW SE NE Sec. 23 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3648'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Woodman & Iannitti Drilling Company

Address: 706 Union National Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 5:00PM Day 27th Month April Year 1966

The Above well was plugged as follows:

270' of 8 5/8" surface pipe, cement circulated with 225 sacks. Hole
was filled with drilling mud to 270', 1st cementing plug, bridged with
1/2 sack of hulls on fluid at 270', and cemented with 25 sacks. Hole was
filled with drilling mud to 40', 2nd cementing plug, bridged with 1/2 sack
of hulls on fluid at 40', and cemented with 10 sacks to the base of the
cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/29/66

INV. NO. 3129-W

Signed: Archie Elving
Well Plugging Supervisor