

KANSAS

Y

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 7 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Intent to Drill,
filed July 24, 1967.

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name J. M. Stewart

Complete Address 608 Union Center Bldg., Wichita, Kansas 67202

Lease Name G. Wetig Well No. # 2

Location SE SE NE Sec. 31 Twp. 21 Rge. 13 (E) (W)

County Stafford Total Depth 3757'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Gabbert-Jones, Inc.

Address 830 Sutton Place, Wichita, Kansas 67202 License No. _____

Operation Completed: Hour 4:30 P.M. Day 3rd Month August Year 1967

The above well was plugged as follows:

305' of 8 5/8" surface pipe, cement circulated with 400 sacks. Hole
had been flowing, and was squeezed. 30 Bbls. of heavy drilling mud
was pumped into the surface pipe and 80 sacks of cement, through an
8 5/8" swage to a pressure of 400 lbs., bringing the cement to the
base of the cellar. A plug was run between the drilling mud and the
cement. This cementing was done by Halliburton Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 8/8/67
INV. NO. 6089-4