

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Inc.

Complete Address Rt. 2 Great Bend, Ks

Lease Name Hickman L-KC Unit Well No. 2-2

Location SW/~~NW~~/NE Sec. 34 Twp. 21s Rge. 14 (E) (W) W

County Stafford Total Depth 3645

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Santa Fe Pipe & Supply Inc.

Address Box 562 Great Bend, Ks License No. 574

Operation Completed: Hour 11:00 AM Day 26 Month 11 Year 1971

The above well was plugged as follows:

250 ft 8 5/8 surface pipe cemented with 125 sacks. 3615 ft 5 1/2 long

string cemented with 125 sacks. Top perf. 3542 ft. Sand back to

3525 ft, 5 sacks cement with bailer. Pulled 2950 ft 5 1/2. Pump 2 sacks

hulls, 15 sacks gel, 100 sacks cement to surface.

Pumped by Globe Cementing Co. Great Bend, Ks

I hereby certify that the above well was plugged as herein stated.

Signed: *[Signature]*
Well Plugging Supervisor

INVOICED

DATE 12-1-71

INV. NO. 4914-W