

4-061020

12-14

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-009-21,782-00-00  
75' N. of  
NE NE NE /4 SEC. 36, 16 S, 12 W  
5025 feet from S section line  
330 feet from E section line

Operator license# 8920

Lease Hoffman "B" Well # 1

Operator: H & M Packer Service

County: Barton

Address: P.O. Box 54  
Ellinwood, Kansas 67526

Well total depth 3332 108.29 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 260 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: D.S. & W. Well Servicing, Inc. License# 6901

Address: P.O. Box 231 - Claflin, Kansas 67525

Company to plug at: Hour: 10:00 A.M. Day: 14 Month: December Year: 1996

Plugging proposal received from: Kent Strube

Company: D.S. & W. Well Servicing, Inc. Phone: 316-587-3361

Were: Order 225 sxs 60/40 posmix - 10% gel and hulls.  
Plug while pulling casing.

12-23-96

Plugging Proposal Received by: Herb Deines


Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 11:30 A.M., Day: 14, Month: December, Year: 1996

Actual plugging report: 8 5/8" to 260 w/200 sxs. 5 1/2" to 3339' w/150 sxs. Perfs 3082' - 3324'. Sanded to 3030' and spotted 5 sxs cement with dump bailer. Pulled stretch on casing and determined that well squeezed below 400'. Decision to plug and leave casing in hole. Cut slots in casing at 1430'- 800'- 400'. Tied onto production casing and pumped 205 sxs cement with 500# hulls. Max. P.S.I. 1000#. S.I.P. 400#. Tied onto annulus and pumped 20 sxs cement. Max. P.S.I. 600#. S.I.P. 200#.

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO   
Bottom plug(in place): YES  CALC , NO  Dakota plug: YES , NO   
Plugged through TUBING , CASING . Elevation: 1897 GL

I did / did not [ X ] observe the plugging.

  
DH (agent)  
Form CP-2/3

INVOICED  
JAN 02 1997

DATE

INV. NO. 47218