

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-19565-00-00
Spot: NESESWNW Sec/Twnshp/Rge: 14-24S-12E
3020 feet from S Section Line, 1300 feet from W Section Line
Lease Name: SULLIVAN Well #: 3
County: GREENWOOD Total Vertical Depth: 1812 feet

Operator License No.: 33861
Op Name: ALLEN'S SERVICE INC. DBA RUDE CR
Address: PO BOX 145
HAMILTON, KS 66853

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1730		
PROD	7	1758		0 SX
SURF	16	16		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/06/2017 8:00 AM
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC
Proposal Revd. from: ALLEN DANNELS Company: _____ Phone: (620) 678-3836

Proposed Plugging Method: Set bridge plug in bottom, cement with 20 sacks. Perforate 2 holes at 700 feet, cement with 20 sacks. Cement from 150 feet to surface on inside and outside of pipe. Set jell bridges between cement.

Plugging Proposal Received By: MICHAEL HEFFERN
Date/Time Plugging Completed: 09/06/2017 11:00 AM

Witness Type: PARTIAL
KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Ran tubing to 1730', pumped 20 sxs cement, pulled tubing to 700', pumped 20 sxs cement, pulled tubing to 151', pumped 105 sxs cement to surface, gel spacers between cement plugs, well shot @ 700' & 250'

Perfs:

Top	Bot	Thru	Comments
1758	1812		

RECEIVED
KCC DIST # 3
SEP 11 2017
CHANUTE, KS

MH

INVOICED
SEP 13 2017

Remarks:

Plugged through: TBG

District: 03

Signed

Michael Heffern
(TECHNICIAN)

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **3527**
 Foreman Russell McLow
 Camp _____

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
9-6-17	1043	Sullivan # 3				G.W	Ks
Customer <u>RUDE CRUDE</u>		Safety Meeting 2m L.K JASU Dave Steve		Unit #	Driver	Unit #	Driver
Mailing Address <u>Box 145</u>				102	RICK		
City <u>HAMILTON</u>		State <u>Ks</u>	Zip Code <u>66653</u>	112	JASU		
				110	DAVE		
				145	STEVE		

Job Type P.T.A. Hole Depth _____ Slurry Vol. _____ Tubing 2 3/8
 Casing Depth _____ Hole Size UNKNOWN Slurry Wt. 13.5 Drill Pipe _____
 Casing Size & Wt. 7" Cement Left in Casing _____ Water Gal/SK 16.5 Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM 14

Remarks: SPOT 20 SKs @ 1730'
SPOT 20 SKs @ 700'
SPOT 105 SKs FROM 150 TO SURFACE
145 SKs TOTAL

NOTE: Gel SPACER Between Plugs
GOLD CEMENT INSIDE + OUT OF 7" FROM 150 TO SURFACE.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-105-2	1	Pump Charge	500.00	500.00
C-107	15	Mileage	3.95	59.25
C-203	145	SKs 60/40 P2mix w/4% Gel	12.75	1848.75
C-108	6.1	TUN TON-M. Mileage	28 m/c.	172.50
C-113	1 hr	EO 801 UAL TRUCK	85.00	85.00
			Sub Total	2,665.50
			7.5 % Sales Tax	199.91
Authorization <u>by Allen Daniels</u> Title <u>owner.</u>			Total	2,865.41

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.