

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-145-20628-00-00  
Spot: SWNESWSW Sec/Twnshp/Rge: 7-20S-20W  
756 feet from S Section Line, 4527 feet from E Section Line  
Lease Name: SMITH Well #: 2-A  
County: PAWNEE Total Vertical Depth: 4395 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3840		WITH 2 SX CMT
PROD	4.5	4399	0	WITH 125 SX CMT
SURF	8.625	460		WITH 300 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/16/2017 12:30 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: SET CIBP ON BOTTOM WITH 2 SX CMT. LOAD HOLE WITH WATER & RUN LOG. IF NO CMT ON BACKSIDE PERFORATE AT ANHYDRITE & SPOT 50 SX CMT WITH 50# HULLS. THEN PERFORATE AT BOTTOM OF SURFACE PIPE & CIRCULATE TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/16/2017 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

8/11/17: RAN BOND LOG & FOUND CMT 450' TO 1350'. TRIED TO GET TO BOTTOM BUT COULDN'T GET BELOW 3872'. 8/16/17: SET CIBP @ 3840' WITH 2 SX CMT. RUN TBG TO 1450' & PUMPED 50 SX CMT & 200# HULLS. CMT WAS AT 600'. PULLED TBG & PERFORATED AT 400'. TIED ONTO CASING & PUMPED 120 SX CMT. CMT CIRCULATED TO PIT.

Perfs:

Top	Bot	Thru	Comments
4372	4376		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

INVOICED  
SEP 13 2017

District: 01

Signed Michael Maier  
(TECHNICIAN)

RECEIVED  
AUG 22 2017  
KCC DODGE CITY

KMS