

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-21014-00-00
Spot: SWNW Sec/Twnshp/Rge: 12-34S-5E
3285 feet from S Section Line, 4756 feet from E Section Line
Lease Name: WALDSCHMIDT C Well #: 1
County: COWLEY Total Vertical Depth: 3070 feet

Operator License No.: 33405
Op Name: ANSTINE & MUSGROVE INC.
Address: PO BOX 391
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3049		200 SX
SURF	8.625	213		135 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/29/2017 8:00 AM
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.
Proposal Rcvd. from: GARY ANSTINE Company: ANSTINE & MUSGROVE Phone: (620) 441-8165

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE WitnessType: PARTIAL
Date/Time Plugging Completed: 08/30/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TUBING @ 3014', QES MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL 2% CC & DISPLACED IN CASING. WAITED 2 HOURS. TAGGED CEMENT 2593'. RIH ON WIRELINE PERFORATED SQUEEZE HOLES & 260'-0'. RIH W/TUBING @ 270', QES ESTABLISHED CIRCULATION. MIXED & PUMPED 144 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
3049	3070	OH	

Remarks: QES TICKET # 54659.

Plugged through: TBG

INVOICED
SEP 18 2017

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

