

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-053-21221-00-00  
Spot: NWSWSESE Sec/Twnshp/Rge: 27-17S-10W  
341 feet from S Section Line, 1000 feet from E Section Line  
Lease Name: SCHEPMANN Well #: 7-27  
County: ELLSWORTH Total Vertical Depth: 3415 feet

Operator License No.: 33770  
Op Name: ARES ENERGY, LTD  
Address: 405 N. MARIENFELD SUITE 250  
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3275		
PROD	5.5	3400		125 SX
SURF	8.625	394		185 SX
T1	2.375	3359		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/06/2017 9:30 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC Phone: (620) 655-4494

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 09/06/2017 3:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL RODS AND TUBING. SET CIBP AT 3275' AND CAP WITH 2 SX'S CEMENT. ATTEMPTED TO CUT CASING TO PULL-COULD NOT. PERFORATE AT 1300', RUN TUBING TO 1300' AND PUMPED 35 SX'S COMMON WITH 3% CC. PULLED TUBING OUT OF HOLE. WAITED 1.5 HRS., TAG CEMENT WITH SAND LINE AT 1150'. PERFORATE AT 950', RUN TUBING TO 950' AND PUMP 35 SX'S COMMON WITH 3% CC. PULL TUBING OUT, WAIT AWHILE AND PERFORATE AT 450', CONNECT ON TO 5.5" AND PUMPED CEMENT GETTING CIRCULATION OF CEMENT TO SURFACE @ 300#'S. WAIT AWHILE AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3323	3342	CSG	

Remarks: THIS WELL IS A TA - N.O.V. WELL. EXCEL WIRELINE #1528. BASIC SERVICES #15323.

Plugged through: TBG

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

INVOICED  
SEP 13 2017