

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-24601-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 3-19S-26W
2395 feet from S Section Line, 3772 feet from E Section Line
Lease Name: THUNDER GULCH Well #: 1-3
County: NESS Total Vertical Depth: 4606 feet

Operator License No.: 31930
Op Name: BLUE RIDGE PETROLEUM CORPORATI
Address: PO BOX 30545
EDMOND, OK 73003

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1449		WITH 200 SX CMT
PROD	5.5	4602	0	WITH 150 SX CMT
SURF	8.625	242		WITH 180 SX CMT

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/18/2017 9:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: RICK POPP Company: BLUE RIDGE PETROLEUM Phone: (620) 786-5514

Proposed Plugging Method: CIBP OR SAND BACK 50' ABOVE PERFS WITH 5 SX CMT ON TOP. TIH WITH TBG TO 1850'. PRESSURE TEST 5 1/2" CASING. FILL 5 1/2" TO SURFACE. CHECK BACKSIDE & FILL WITH CMT.

Plugging Proposal Received By: KEN SCOFIELD Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/18/2017 1:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4517' & PUMP 50 SX CMT & 200# HULLS. PULL TBG TO 1854' & PUMP 160 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 20 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4504	4515		
4496	4515		

INVOICED
SEP 13 2017

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: TBG

District: 01

Signed Michael Maier
(TECHNICIAN)

LM5