

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-22429-00-00
Spot: SENWSESW Sec/Twnshp/Rge: 36-19S-9W
674 feet from S Section Line, 3322 feet from E Section Line
Lease Name: REED 19-9 Well #: 1-36
County: RICE Total Vertical Depth: 3450 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2080		
COND	14000	40		
PROD	5.5	3436		180 SX
SURF	8.625	231		158 SX
T1	2.375	2095		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/06/2017 1:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 09/06/2017 3:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

PREVIOUS CIBPS SET @ 2890', 2345' & 2140'. MIRU, SET CIBP AT 2080' AND CAP WITH 5 SX'S CEMENT. PERFORATE AT 1150', 750', AND 280'. RUN TUBING TO 1150' AND PUMP 35 SX'S COMMON WITH 2% CC. PULL TUBING UP TO 750' AND WAIT 1 HOUR. TAG CEMENT AT 800'. PUMP 35 SX'S COMMON WITH 2% CC AT 750', PULL TUBING TO 280' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
2989	2994	CSG	
2955	2960	CSG	
2908	2912	CSG	
2424	2441	CSG	
2413	2418	CSG	

Remarks: DENIED TA WELL. GRESSELL PERF #1589. COPELAND CEMENT #C-45596.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
SEP 14 2017