

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-20328-00-00
Spot: NENESWNE Sec/Twnshp/Rge: 33-21S-33W
1390 feet from N Section Line, 1390 feet from E Section Line
Lease Name: WEINMAN Well #: 1
County: FINNEY Total Vertical Depth: 3341 feet

Operator License No.: <u>5317</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>FREEMAN, RUSSELL DBA CONTINENT</u>	CIBP		2500		WITH 40 SX CMT
Address: <u>PO BOX 918</u>	PROD	4.5	3322	0	WITH 600 SX CMT
<u>GARDEN CITY, KS 67846</u>	SURF	8.625	650		WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/30/2017 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: DAVID Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/30/2017 6:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2500' WITH 40 SX CMT ON TOP UP TO 1900' TO COVER THE STONE CORRAL. RAN CBL FROM 1210' TO 10'. TOC @ 180'. RUN TBG TO 1071' & CIRCULATE CMT TO SURFACE WITH 80 SX CMT. TOP OFF 4 1/2" WITH 13 SX CMT. PUMP 35 SX CMT DOWN THE ANNULUS. PRESSURE TO 200#. HOLDING.

Perfs:


Top	Bot	Thru	Comments
2596	2616		
2572	2578		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
SEP - 7 2017
KCC DODGE CITY



5A

INVOICED
SEP 15 2017