

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-22034-00-00
Spot: NWSESE Sec/Twnshp/Rge: 21-23S-13E
990 feet from S Section Line, 990 feet from E Section Line
Lease Name: JONES Well #: 33
County: GREENWOOD Total Vertical Depth: 1850 feet

Operator License No.: 33640
Op Name: HAAS PETROLEUM, LLC
Address: 10551 BARKLEY ST. #307
OVERLAND PARK, KS 66212

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD | 4.5 | 1834 | | 119 SX |
| SURF | 8.625 | 34 | | 9 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/07/2017 10:00 AM
Plug Co. License No.: 33557 Plug Co. Name: SKYY DRILLING, LLC
Proposal Rcvd. from: MARK HAAS Company: _____ Phone: (913) 499-8373

Proposed Pumping Method: Pump full of cement from bottom to top

Plugging Proposal Received By: MICHAEL HEFFERN
Date/Time Plugging Completed: 09/07/2017 1:00 PM

WitnessType: COMPLETE (100%)
KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

ran tubing to 1710', pumped 20 sxs cement pulled tubing to 800' pumped 20 sxs cement, pulled tubing to 250' pumped 25 sxs cement to surface, gel spacers between cement plugs, casing shot @ 800' & 250'

RECEIVED
KCC DIST # 3
SEP 11 2017
CHANUTE, KS

MH

Remarks:

Plugged through: TBG

District: 03

Signed

Michael Heffern

(TECHNICIAN)

INVOICED
SEP 15 2017

Form CP-2/3



PRESSURE PUMPING LLC
PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

TICKET NUMBER 53871

LOCATION Orbance KS

FOREMAN Fred Maden

FIELD TICKET & TREATMENT REPORT
CEMENT

15-073-22034 over

| DATE | CUSTOMER # | WELL NAME & NUMBER | SECTION | TOWNSHIP | RANGE | COUNTY |
|----------------------|------------|--------------------|---------|----------|-------|--------|
| 9-7-17 | 3451 | Jones #23 | 0E 21 | 22 | 13 | W |
| CUSTOMER | | | TRUCK # | | | |
| Haas Petroleum LLC | | | DRIVER | | | |
| MAILING ADDRESS | | | TRUCK # | | | |
| 10551 Barkley St 307 | | | DRIVER | | | |
| CITY | | | TRUCK # | | | |
| STATE | | | DRIVER | | | |
| ZIP CODE | | | TRUCK # | | | |
| Overland Park | | | DRIVER | | | |
| KS | | | TRUCK # | | | |
| 66212 | | | DRIVER | | | |

JOB TYPE Plug HOLE SIZE — HOLE DEPTH — CASING SIZE & WEIGHT 4 1/2
 CASING DEPTH 1710' DRILL PIPE 1" TUBING 1710' OTHER —
 SLURRY WEIGHT — SLURRY VOL — WATER gal/sk — CEMENT LEFT in CASING Full
 DISPLACEMENT N/A DISPLACEMENT PSI — MIX PSI — RATE 1-1 1/2 BPM

REMARKS: Hold Safety Meeting. Rig run 1" tubing to TD. Mix 11.5 BBLs Gelled Water. Follow w/ 20 sks Cement. Displace to TD. Pull 1" tubing to 800'. Mix 5.5 BBL Gelled Water. Follow w/ 20 sks Cement. Displace to 800'. Pull 1" tubing to 250'. Fill to Surface w/ Cement. Pull remaining 1" tubing. Top off Well w/ Cement. Wash out 1" tubing.

Customer Supplied Water Fred Maden

| ACCOUNT CODE | QUANTITY or UNITS | DESCRIPTION of SERVICES or PRODUCT | UNIT PRICE | TOTAL |
|--------------|-------------------|------------------------------------|-------------------|-----------------------|
| CE0450 | 1 | PUMP CHARGE | 495 | 1500 ⁰⁰ |
| CE0002 | 35 mi | MILEAGE | 495 | 258 ²⁵ |
| CE0711 | Minimum | Ten Miles Delivery | 558 | 660 ⁰⁰ |
| | | Sub Total | | 2410 ²⁵ |
| | | Less 40% | | 1446 ¹⁵ |
| CC5840 | 60 sks | Por Blend IA Cement | 810 ⁰⁰ | |
| CC5765 | 702* | Bentonite Gel | 210 ⁰⁰ | |
| | | Sub Total | | 1020 ⁰⁰ |
| | | Less 40% | | 612 ⁰⁰ |
| | | 7.5% | SALES TAX | 45 ⁹³ |
| | | | ESTIMATED TOTAL | \$2104 ⁴⁴ |
| | | | | (3507 ³⁹) |

Revised 9737 AUTHORIZATION [Signature] TITLE — DATE —

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.