

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-171-20977-00-00
Spot: SESWNESW Sec/Twnshp/Rge: 23-19S-31W
1423 feet from S Section Line, 3527 feet from E Section Line
Lease Name: SUPPES Well #: 1
County: SCOTT Total Vertical Depth: 4560 feet

Operator License No.: 32158
Op Name: H & B PETROLEUM CORP.
Address: PO BOX 1305
HUTCHINSON, KS 67504

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4240		WITH 2 SX CMT
CIBP		4560		
PROD	5.5	4707	0	WITH 730 SX CMT
SURF	8.625	325		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/23/2017 9:00 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: MIKE Company: H&B PETROLEUM Phone: (620) 259-6713

Proposed Plugging Method: CIBP @ 4240' WITH 2 SX CMT. PLUG AT 2350' CIRCULATE CMT TO SURFACE. CHECK ANNULUS.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/23/2017 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4240' WITH 2 SX CMT. RUN TBG TO 2338'. CIRCULATE CMT TO SURFACE USING 210 SX CMT. TOP OFF 5 1/2" CASING WITH 25 SX CMT. PUMP 3 SX CMT DOWN THE ANNULUS TO 300#.

Perfs:


Top	Bot	Thru	Comments
4629	4635		

Remarks: USED 60/40 POZMIX 4% GEL BY GLOBAL.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN) INVOICED

RECEIVED
AUG 24 2017
KCC DODGE CITY

SEP 15 2017

Form CP-2/3

KMS