

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-155-21168-00-00
Spot: NWSENEW Sec/Twnshp/Rge: 29-23S-10W
4327 feet from S Section Line, 3097 feet from E Section Line
Lease Name: BOWEN Well #: 1
County: RENO Total Vertical Depth: 3860 feet

Operator License No.: 31958
Op Name: HESSE PETROLEUM CO., L.L.C.
Address: 400 N WOODLAWN STE 7
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3848	2362	150 SX
SURF	8.625	228		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/03/2017 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: _____ Phone: (316) 605-4746

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 07/03/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Perfs:

SANDED BACK TO 3500', CAPPED WITH 5 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 2362' PULLED CASING TO 1458' SPOTTED 50 SX CEMENT. PULLED CASING, WAITED 2 HOURS TAGGED WITH SAND LINE @ 1400', RAN TUBING TO 932' SPOTTED 35 SX CEMENT. PULLED TUBING TO 280' CIRCULATED TO SURFACE WITH 137 SX CEMENT. CEMENT FELL 18' CAPPED WITH 5 SX CEMENT.

Remarks: CEMENT PROVIDED BY COPELAND OUT OF GREAT BEND. PAST TEN YEAR TA.

Plugged through: CSG

District: 02

Signed B. J. Hope

(TECHNICIAN)

INVOICED
SEP 15 2017

Form CP-2/3

✓