

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-30633-00-00
Spot: SWNENE Sec/Twnshp/Rge: 27-25S-8E
990 feet from N Section Line, 990 feet from E Section Line
Lease Name: HAWTHORNE Well #: 4
County: GREENWOOD Total Vertical Depth: 2605 feet

Operator License No.: 5697
Op Name: JACKSON BROTHERS, L.L.C.
Address: 116 E 3RD ST.
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2605		75 SX
SURF	8.625	131		75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/31/2017 11:00 AM
Plug Co. License No.: 6112 Plug Co. Name: LONG DRILLING COMPANY, LLC
Proposal Rcvd. from: ROSCOE G. JACKSON II Company: _____ Phone: (620) 583-5122

Proposed Plugging Method: 1. 50-ft. cement plug inside 4.500" casing at 2530-2480 ft. 2. 50-ft. cement plug inside and outside 4.500" at 1290-1240 ft. 3. Continuous cement plug inside and outside 4.500" from 250 ft. to land surface.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: NONE
Date/Time Plugging Completed: 09/05/2017 1:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran dump baler to 2530', dumped 7 sxs cement, set rock bridge @ 1290' ran tubing to 1290' pumped 20 sxs cement, pulled pipe out built rock bridge @ 250', ran tubing pumped 95 sxs cement to surface, gel spcers between cement plugs

Perfs:

Top	Bot	Thru	Comments
2563	2567		

RECEIVED
KCC DIST # 3
SEP 11 2017
CHANUTE, KS

MH

Remarks:

Plugged through: TBG

District: 03

Signed

Mike [Signature]
(TECHNICIAN)

INVOICED

SEP 15 2017

Form CP-2/3

810 E 7th
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Received 5 Sept 2017

Cement or Acid Field Report
 Ticket No. **3526**
 Foreman Russell McLow
 Camp EUREKA

Date	Cust ID #	Lease & Well Number	Section	Township	Range	County	State
9-5-17	1000	Hawthorne # 4	27	25S	8E	G.W	KS
Customer JACKSON BROTHERS L.L.C.			Safety Meeting Pm Pm AB Dove		Unit # 102 110 141	Driver Rick AB Dove	Unit # Driver
Mailing Address 116 E. THIRD			City EUREKA		State KS	Zip Code 67045	

Job Type PTA Hole Depth _____ Slurry Vol _____ Tubing 2 3/8 1290'
 Casing Depth _____ Hole Size 6 3/4" Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 4 1/2" Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks Safety meeting SPRT 20 SKS @ 1290'
 SPRT 75 SKS @ 25' TO SURFACE IN ROUTINE
 95 SKS TOTAL OF 4 1/2"

NOTE Gel spacer between 1290 + 300'
 Build bridge w/ Rig @ 300'
 Good cement Return wait 1 hr top off well well stayed Full
 Job complete Tear down. Bottom plug set by Long Drig
 Thank you
Russell McLow

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-105	1	Pump Charge	750.00	750.00
C-107	15	Mileage	3.95	59.25
C-203	95	SKS 6 1/4" PUMIX	12.75	1211.25
C-206	300 ^{ft}	Gel	.20	60.00
C-108a	4 Trk	Tow Mileage Bull Truck	m/c	345.00
C-113	3	hr Eq. Bul UAC Truck	ES.00	255.00
			-59% DISCOUNT	-\$144.08
			Sub Total	2667.50
			Sales Tax	266.74

Authorization Roscoe Jackson II Title CO-MANAGER Total 2,934.24
\$2,737.46

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.