

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-101-22018-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 1-16S-27W  
4387 feet from S Section Line, 2321 feet from E Section Line  
Lease Name: CURTIS-WEEKS Well #: 1-1  
County: LANE Total Vertical Depth: 4590 feet

Operator License No.: 6039  
Op Name: L. D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1978		WITH 400 SX CMT
PROD	4.5	4589	0	WITH 200 SX CMT
SURF	8.625	208		WITH 160 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/22/2017 10:00 AM

Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP

Proposal Rcvd. from: GERALD WALKER Company: LD DRILLING Phone: (620) 793-3051

Proposed Plugging Method: SQUEEZE PERFS 25 SX CMT & 200# HULLS. PLUG AT 2010' WITH CMT TO 0'. CHECK BACKSIDE WITH CMT TO 500#.

Plugging Proposal Received By: KENNY SULLIVAN

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 08/22/2017 3:00 PM

KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 25 SX CMT & 200# HULLS AT 4413'. PULL TBG TO 2109' & LOAD HOLE.  
CIRCULATE CMT TO SURFACE USING 140 SX CMT. PULL TBG & TOP OFF WITH 40  
SX CMT. PUMP 60 SX CMT DOWN THE ANNULUS TO 200#.

Perfs:

Top	Bot	Thru	Comments
4424	4428		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: TBG

District: 01

Signed \_\_\_\_\_

*Ken Jehlik*  
(TECHNICIAN)

RECEIVED  
AUG 24 2017  
KCC DODGE CITY

*MP*

INVOICED  
SEP 15 2017

Form CP-2/3

*VMS*